

# Rootball Watering- Urban/ Park System Installation Instructions

---

## **Planting**

Plant the tree as normal, backfilling to approximately 300mm below final ground level. Remember to allow for mulch.

## **Laying the pipe**

Lay pipe in loop around the root ball system trimming pipe length to ensure snug fit in the tree pit. Pipe should be laid in a loop as near to horizontal as practical in site conditions. Both ends of the pipe should then be connected into the plastic tee junction. Ensure that pipes are pushed in at least 50mm.

The inlet should be not more than 50mm above finished surface levels.

## **Backfilling**

When the Park system is assembled, backfill layers firming gently over the pipe. Grid top should protrude slightly to prevent ingress of mulch or earth.

